

MATERIALS		QTY.	UNIT	UNIT COST	TOTAL COST
<b>I. FOOTING WORKS</b>					
	Cement	12	bags		
	Sand	1	cu.m		
	16mm Ø DSB x 6.0m	13	pcs		
	Gravel	2	cu.m		
	#16 GI Wire	1	kgs		
Sub-total					-
<b>II. COLUMN WORKS</b>					
	Cement	15	bags		
	Sand	1	cu.m		
	Gravel	2	cu.m		
	16mm Ø DSB x 6.0m	24	pcs		
	10mm Ø DSB x 6.0m	22	pcs		
	#16 GI Wire	7	kgs		
Sub-total					-
<b>III. BEAMWORKS</b>					
	Cement	8	bags		
	Sand	1	cu.m		
	Gravel	1	cu.m		
	16mm Ø DSB x 6.0m	13	pcs		
	10mm Ø DSB x 6.0m	14	pcs		
	#16 GI Wire	5	kgs		
Sub-total					-
<b>IV. SLAB</b>					
	Cement	40	bags		
	Sand	5	cu.m		
	Gravel	6	cu.m		
	10mm Ø DSB x 6.0m	5	pcs		
	#16 GI Wire	2	kgs		
Sub-total					-
<b>V. CHB WALL</b>					
	5" Thk CHB	20	pcs		
	Cement	20	bags		
	Sand (Mortar and Filler)	30	cu.m		
	10mm Ø DSB x 6.0m	4	pcs		
	#16 GI Wire	18	kgs		
Sub-total					-
<b>VI. PLASTERING</b>					
	Cement	39	bags		
	Sand	4	cu.m		
Sub-total					-
<b>VII. FINISHES</b>					
	Flag Stone	9	sq.m		
	100mm x 100mm Tubular Stainless Steel	23	pcs		
	Welding Rod (Stainless)	4	kgs		
	Grinding Disc	2	pcs		
	Cement	6	bags		
	Sand	2	cu.m		
Sub-total					-
<b>VIII. STEEL TRUSER</b>					
	3" x 3" x 1/4" x 6m Angle Bar	8	pcs		
	2" x 2" x 3/6" x 6m Angle Bar	24	pcs		
	Welding Rod	10	kgs		
	Cutting Disc	4	pcs		