

MATERIALS		QTY.	UNIT	UNIT COST	TOTAL COST
<b>I Column and Column Footing (Concrete and Re-bars Works)</b>					
	Cement	8	bags		
	Washed Sand	0.5	cu.m		
	Gravel	1	cu.m		
	12mm Ø DSB x 6.0m	11	pcs		
	10mm Ø DSB x 6.0m	10	pcs		
	#16 GI Wire	3	kgs		
				<b>Sub-Total</b>	
<b>II Slab</b>					
	Cement	8	bags		
	Washed Sand	0.5	cu.m		
	Gravel	1	cu.m		
	10mm Ø DSB x 6.0m	8	pcs		
	#16 GI Wire	1	kgs		
				<b>Sub-Total</b>	
<b>III Post</b>					
	100 Ø 6mm Thk. Steel Column x 6.0m	2	pcs		
	16mm Ø Anchor Bolt	16	pcs		
	0.25m x 0.25m x 0.10mm Steel Plate	4	pcs		
				<b>Sub-Total</b>	
<b>IV Trusses and Roofing</b>					
	1 1/2" x 1 1/2" x 6m Angle Bar	7	pcs		
	1" x 1" x 6m Angel Bar	8	pcs		
	Welding Rod	5	kgs		
	Cutting Disc #4"	5	pcs		
	C-purlins 2" x 4" x 6m	6	pcs		
	Tile Span Roofing x 3.2m	4	pcs		
	75 x 150 x 10mm Thk Stiffener plate	8	pcs		
	10mm thk Steel top plate	4	pcs		
	P.E. Foam Insulator 10mm double cde	5.7	sq.m		
	ledge	1.14	sq.m		
				<b>Sub-Total</b>	
<b>V Doors and Windows and Wall</b>					
	0.80 x 2.10 Steel Door w/ 5mm Thk Clear Fixed Glass	1	set		
	1.975 x 1.31m L-Type Window w/ 5mm Thk Clear Glass on Powder Coated Alluminum Frame	1	set		
	0.775 x 1.30m L-Type Window w/ 5mm Thk Clear Glass on Powder Coated Alluminum Frame	1	set		
	1.26m Awing Type Window 2/ 5mm Thk Clear Glass on Powder Coated Alluminum Framing	1	set		
	100mm Thk Polycarbonate Double Wall Panel	48.14	sq.m		
				<b>Sub-Total</b>	
<b>VI Painting Works</b>					
	Primer Paint	2	gal		
	Paint Thinner	2	gal		
	Flat Wall Enamel	5	gal		
	Semi Gloss Enamel	5	gal		