

**PROJECT TITLE: IMPROVEMENT OF MATERIAL RECOVERY FACILITY AT PPSC HEAD OFFICE****LOCATION: MWSS Compound, Old Balara, Quezon City**

MATERIALS		QTY.	UNIT	UNIT COST	TOTAL COST
<b>I. CONCRETE WORKS + REBARS + COLUMN</b>					
12mm Ø DSB x 6.0m		18	pcs		
10mm Ø DSB x 6.0m		38	pcs		
6" Ø GI Pipe		5	pcs		
Gravel		5	cu.m		
Sand		3	cu.m		
Cement		30	bags		
16 GI Wire		5	kgs		
Welding Rod		6	kgs		
1/2 Plywood		3	pcs		
Assorted Nails		3	kgs		
Anchor Bolts		30	pcs		
0.3 x 0.3 Steel Plate		8	pcs		
				Sub-total	-
<b>II. WALL, FRAME, ROOF FRAME + ROOFING</b>					
1 1/2 x 1 1/2 Angle Bar		6	pcs		
1" x 1" Angle Bar		6	pcs		
2 x 3 C Purlins		9	pcs		
2 x 4 C Purlins		23	pcs		
12' Ribtype Roofing		8	pcs		
8' Corr GI Sheet		29	pcs		
2/2' Tek screw		285	pcs		
Rivets		450	pcs		
Sealant		2	liter		
1" x 10" x 10' Facia Board Hardiflex		6	pcs		
Black Screw		60	pcs		
				Sub-total	-
<b>III. PAINTING WORKS</b>					
Flat Wall Enamel		12	ltr		
Gloss Enamel		12	ltr		
Red Oxide		3	ltr		
Paint Roller		3	set		
Paint Brush 2"		3	pcs		
Paint Thinner		2	gal		
Tingting Color		5	pint		
Sand Paper		9	pcs		
				Sub-total	-