

PROJECT TITLE: RGMF of GSS and Supply Office Upgrading of Power Layout to 400V,
 and Installation of Lighting Fixtures and Additional Aircon Layout.

LOCATION: MWSS, PPSC HEAD OFFICE, OLD BALARA QUEZON CITY

MATERIALS

QTY.

UNIT

UNIT COST

TOTAL COST

ELECTRICAL WORK

1	1 GANG SWITCH w/ COVER	14	sets
2	2 GANG SWITCH	4	sets
3	3 GANG SWITCH w/ COVER	3	sets
4	CONVENIENCE OUTLET W/ GROUP	27	sets
5	JUNCTION BOX 4"x4"	12	pcs
6	PLASTIC MOULDING 3/4"	200	pcs
7	AMCO BOX	50	pcs
8	3/4" DIA. CLAMP	200	pcs
9	3/4" DIA. ELBOW	20	pcs
10	3/4" DIA. PVC PIPE	100	pcs
11	3/4" DIA. PVC ADAPTOR W/ COUPLING AND BUSHING	20	pcs
12	40 WATTS FLUORESCENT TUBE	60	pcs
13	2X18 WATTS LED FLUORESCENT LAMP	26	sets
14	PIN LIGHTS LED 8 WATTS	57	pcs
15	30 AT/ 400V / 3P CIRCUIT BREAKER	6	pcs
	IN NEMA 3R ENCLOSURE		
16	2" DIA. PIPE	11	pcs
17	2" DIA. ELBOW	2	pcs
18	2" DIA. PUL ADAPTOR / COUPLING AND BUSHING	2	pcs
19	3.5 MM2 THHN	7	roll
20	5.5 MM2 THHN BLACK	3	roll
21	5.5 MM2 THHN GREEN	1	roll
22	30MM2 THHN	180	mtr
23	8MM2 THHN	50	mtr
24	MAIN POWER	1	asst
	1PC MAIN 100AT/ 125AF/ 3P		
	10PCS 20 AT/ 50AF/ 1P/ 230V		
	6PCS 30AT/ 50AF/ 3P/ 400V		
25	PLASTICLIGHT DIFFUSER 0.6 X 1.2M	14	pcs

Sub-total

MATERIAL COST

LABOR

DIRECT COST

OCM

PROFIT

INDIRECT COST


TAXES

TOTAL PROJECT COST

SCOPE OF WORKS

1	INSTALLATION OF PANEL BOARD
2	INSTALLATION OF ELECTRICAL LINES AND FIXTURES

Prepared by:



ENGR. ULYSSES R. MALAPITAN
 Registered Electrical Engineer

Noted By:



ENGR. RICHEL B. VIRAY
 Chief, Engineering Unit, GSS