



# MEMORANDUM

FOR : CHAIRMAN, BIDS AND AWARDS COMMITTEE  
 Attention : BAC Secretariat

FROM : CHIEF, GENERAL SERVICES SECTION

SUBJECT : MODIFIED TECHNICAL SPECIFICATION OF SOIL TEST TO BE CONDUCTED FOR THE FY 2019 CONSTRUCTION OUTLAY

DATE : 15 JANUARY 2019

-----  
 Below are the following modified technical specifications for the Geotechnical Soil Test of PPSC Construction Projects:

1. No. of Boreholes : 2
2. Depth requirement from natural ground level: 15 meters;

Additional Specifications:

3. Exact Address of the Project/or Project Location;
  4. Latitude of the Project Location;
  5. Longitude of the Project Location;
  6. Zip Code of the Project Location;
  7. Distance of the project location from the nearest fault line;
  8. Near Source Factor (Na) based on 2015 NSCP;
  9. Near Source Factor (Nv) based on 2015 NSCP;
  10. Siesmic Coefficient Factor (Ca) based on 2015 NSCP;
  11. Siesmic Coeficient Factor (Cv) based on 2015 NSCP;
  12. Soil Type of project location;
  13. Soil Classification of project location;
  14. Result of Soil Pressure of the project location at 2meters depth;
  15. Result of Soil Pressure of the project location at 3meters depth;
  16. Result of Soil Pressure of the project location at 4 meters depth.
- Duration: 24 calendar days from receipt of notice to proceed work (NTP)

Prepared by:

  
**DOSMEDO G. TABRIELA, MPSA**  
 Engineer III (Civil/Structural)

Noted:

  
**QUENNIE G. BIONA, LIB**  
 Chief, General Services Section 