

**PROJECT TITLE: Improvement of Gate and Fence @ National Forensic Science Training Institute**  
**LOCATION: Camp Vicente Lim, Canlubang, Laguna**

MATERIALS	QTY.	UNIT	UNIT COST	TOTAL COST
-----------	------	------	-----------	------------

**I EXCAVATION WORKS**

Excavation	69.62	cu.m		-
<b>Sub-Total</b>				-

**II Column Footing (Concrete)**

Cement	98	bags		-
Sand	4	cu.m		-
Gravel	8	cu.m		-
Gravel Bed	1	cu.m		-
<b>Sub-Total</b>				-

**III Column Footing (Rebars)**

12mm Ø DSB x 6.0m	62	pcs		-
#16 GI Wire	4	kgs		-
<b>Sub-Total</b>				-

**IV Wall Footing**

Cement	21	bags		-
Sand	2	cu.m		-
Gravel	1	cu.m		-
10mm Ø DSB x 6.0m	27	pcs		-
#16 GI Wire	4	kgs		-
<b>Sub-Total</b>				-

**V Column (Concrete and Rebars)**

Cement	54	bags		-
Sand	2	cu.m		-
Gravel	4	cu.m		-
16mm Ø DSB x 6.0m	58	pcs		-
10mm Ø DSB x 6.0m	150	pcs		-
#16 GI Wire	25	kgs		-
<b>Sub-Total</b>				-

**VI CHB WALL**

Cement	20	bags		-
Sand	3	cu.m		-
150mm THK Chb	919	pcs		-
10mm Ø DSB x 6.0m Dowel	107	pcs		-
#16 GI Wire	3	kgs		-
Plastering	65	sq.m		-
<b>Sub-Total</b>				-

**VII FORMWORKS**

4' x 8' x 3/4" Thk Phenolic Board	6	pcs		-
2' x 3' x 12' Coco lumber	63	pcs		-
CW Nail #3"	4	kgs		-
CW Nail #2"	2	kgs		-
CW Nail #1 1/2"	2	kgs		-
<b>Sub-Total</b>				-

**VIII TUBULAR FENCE**

2' x 2" x 6m Tubular	89	pcs		-
Cutting Disc	7	pcs		-
Welding Rod	23	kgs		-
Grinding Disc	4	pcs		-
<b>Sub-Total</b>				-

**IX PAINTING WORKS**

Primer Paint	7	gals		-
Enamel Paint	7	gals		-
Semi Gloss enamel Paint	7	gals		-
Paint Thinner	3	gals		-
Tinting Color	7	litrs		-