

					0.80 x 2.10 Steel Door w/ 5mm Thk Clear Fixed Glass		1	set		-
F	Doors and Windows and Wall									
									Sub-Total	-
					ledge		1.14	sq.m		-
					P.E. Foam Insulator 10mm double cde		4	sq.m		-
					10mm thk Steel top plate		3	pcs		-
					75 x 150 x 10mm Thk Stiffener plate		7	pcs		-
					Tile Span Roofing x 3.2m		3	pcs		-
					C-purlins 2" x 4" x 6m		5	pcs		-
					Cutting Disc #4"		4	pcs		-
					Welding Rod		4	kgs		-
					1" x 1' x 6m Angel Bar		7	pcs		-
					1 1/2" x 1 1/2" x 6m Angle Bar		6	pcs		-
D	Trusses and Roofing									
									Sub-Total	-
					0.25m x 0.25m x 0.10mm Steel Plate		4	pcs		-
					16mm Ø Anchor Bolt		14	pcs		-
					100 Ø 6mm Thk. Steel Column x 6.0m		2	pcs		-
C	Post									
									Sub-Total	-
					#16 GI Wire		1	kgs		-
					10mm Ø DSB x 6.0m		7	pcs		-
					Gravel		1	cu.m		-
					Washed Sand		0.5	cu.m		-
					Cement		7	bags		-
B	Slab									
									Sub-Total	-
					#16 GI Wire		2	kgs		-
					10mm Ø DSB x 6.0m		12	pcs		-
					12mm Ø DSB x 6.0m		18	pcs		-
					Gravel		1	cu.m		-
					Washed Sand		0.5	cu.m		-
					Cement		7	bags		-
A	Column and Column Footing (Concrete and Re-bars Works)									
XIII	Guard House									
									Sub-Total	-
					Welding rod		30	kgs		-
					Cutting disc		10	pcs		-
					70mm x 70mm Tubular Steel Bar		29	pcs		-
					2" x 2" Tubular Steel Frame		161	pcs		-
XII	Entrance Gate									
									Sub-Total	-
					Sand		2	cu.m		-
					Stone Cladding		52	sq.m		-
					Cement		10	bags		-
XI	Stone Cladding									
									Sub-Total	-
					#16 GI Wire		4	kgs		-
					10mm Ø DSB x 6.0m		70	pcs		-
					Gravel		15	cu.m		-
					Sand		8	cu.m		-
					Cement		137	bags		-
X	Concrete Entrance									
									Sub-Total	-
					Paint Brush #3		9	pcs		-
					Paint Roller #4"		7	pcs		-
					Paint tray		3	pcs		-
					Cloth (rug)		9	kgs		-