



Republic of the Philippines
Department of the Interior and Local Government
PHILIPPINE PUBLIC SAFETY COLLEGE
MWSS Compound, Katipunan Avenue cor. Ayala Heights
Old Balara, Quezon City



NFTI, Camp Vicente Lim, Canlubang, Laguna

SCOPE OF WORKS

Rehabilitation of Existing Wooden Grandstand with Bleacher

1. Mobilization / Installation of Bunkhouse / Delivery of Materials
2. Demolition of Existing Wooden Grandstand with Bleacher Structure
3. Staking / Excavation of Column Footing
4. Fabrication and Installation of Steel for Column Footing and Column
5. Fabrication and Installation of Forms and Scaffoldings
6. Pouring of Concrete for Column Footing and Column
7. Installation of CHB Walls and Dowels with Plastering
8. Fabrication and Installation of Steel Bars for Beams
9. Fabrication and Installation of Forms and Scaffoldings for Beam
10. Installation of Earth filling materials and Compaction
11. Installation of Plumbing, Water Lines and Fixtures
12. Installation of Electrical Rough-in, Electrical Lines and Fixtures
13. Installation of Bars and Concreting of Slab
14. Fabrication and Installation of Steel Trusses, Purlins and Color roof Rib-type Roofing
15. Installation of Floor and Wall Tiles
16. Fabrication and Installation of Stainless Railing
17. Installation of ARAAL Stone for Building Frontage
18. Installation of Heat Installation, Chicken Wires and Ceiling Board
19. Painting Works
20. Testing of Electrical Works, Plumbing Works and Water Lines
21. Excavation and Installation of CHB Walls for Septic Tank
22. Clearing / Demobilization


Other Requirements:

1. The Duration of Work is One Hundred Fifty (150) Calendar Days
2. All Contractor's personnel to be assigned to the project must possess a Negative Covid-19 Polymerase Chain Reaction (PCR) Test Certificate to be submitted at the time of entry of personnel
3. The Contractor's Occupational Safety and Health Programs must include the adoption of Covid-19 minimum health standards and protocols

Prepared by:


NICOMEDES A. PASCUAL
PPSC Technical Inspector

Submitted by:


ENGR. ROMY V. YALO
Acting Chief, GSS, AD