

- Chipping and restoration of wall to provide access for the hauling/positioning/repositioning of the unit onsite at the building's designated area.
- Supply of liquid consumable (engine oil)
- Installation of power cable from GENSET to Automatic Transfer Switch (ATS), cable pulling and termination.
- Installation of Flexible pipe and ATS, mounting
- Installation of exhaust pipe extension with testing port
- Installation of cladding and muffler and exhaust pipe exhaustion
- Labor and restoration onsite include civil and mechanical works (Unit must be elevated at a minimum of 0.20 meter above the base ground level)
- Supply of rubber Vibro Isolator
- Hands-on training of at least two (2) authorized personnel from the PPSC on proper operation and preventive maintenance.
- Comprehensive Operation and Maintenance Manual
- The GENSET should be tested by operation it continuously at a minimum of four (4) hours but not to exceed eight (8) hours.
- Provide supply of diesel fuel to the GENSET during the entire duration of testing (free of charge).
- On-site PPSC HO and NPC-Silang commissioning and testing of unit. Testing and commissioning shall be conducted by the supplier's technical representatives and must be witnessed by the PPSC HO and NPC-Silang authorized/designated representatives.
- During the testing and commissioning the necessary standard parameters must be met, otherwise, the PPSC HO and NPC-Silang authorized representatives may stop the testing and declare it as failed.
- Installation of radiator ducting.

8. Terms and Conditions

- The procuring entity shall impose penalty of 1/10 of 1% of the total value of the undelivered order or each day of delay as liquidated damaged after the specified allowable number of days to deliver the unit/items.
- Non-availability of stock/item shall be made to procuring entity before the acceptance of the Notice to Proceed (NTP).
- The PPSC HO and NPC- Silang shall have the right to reject and return the items and cancel the corresponding Contract of goods delivered which are found to be defective, incomplete or non-compliant to the specifications herein specified.
- Deliveries should be made within office hours and on regular working days on or before the stipulated date in the Purchase Order (PO) unless otherwise specified for valid reason why the same cannot be complied with.

9. Warranty

The GENSET shall carry on one (1) year or twelve (12) months warranty on parts and services commencing on the date of commissioning, against factory defects under normal operating conditions.

10. Delivery

The generator sets including all items and its accessories must be delivered within sixty (60) calendar days after receipt of the Notice to Proceed (NTP). Two (2) units will be delivered to PPSC HO and also two (2) units will be delivered to NPC-Silang.